

THE PORT AUTHORITY OF NY & NJ

**PROCUREMENT DEPARTMENT
2 MONTGOMERY STREET, 3RD FL.
JERSEY CITY, NJ 07302**

11/20/2014

ADDENDUM # 3

**To prospective Bidder(s) on Bid # 40170 WIRE ROPE SUSPENDER PROGRAM GWB
FOR THE GEORGE WASHINGTON BRIDGE.**

Due Back on 12/02/2014, no later than 11:00AM
(Originally due back on 11/20/2014, no later than 11:00AM)

NOTE: NEW BID DATE AS: 12/02/2014, NO LATER THAN 11:00AM

NOTE: The following changes:

**REQUEST FOR QUOTATION (RFQ) FORM PAGE 2 OF 6.
ITEM 2 INSERT THE FOLLOWING:**

Item 2: AFTER THE WORDSat each end.

INSERT: "and installation of zinc buttons".

and

ITEM 2: AFTER THE WORDS "Cut & cap with 2 sockets:

INSERT: "and 2 zinc buttons" per section.

ATTACHMENT ENTITLED "Description of Purchase Order"

DELETE THE THIRD BULLET AS originally stated and replace in its entirety the following:

- Cutting fabricated wire rope to the specified length, **marked as specified in Attachment A, installation of** pair of galvanized carbon steel Type 8 Anchor socket machined from steel conforming to ASTM A576 and galvanized in accordance with ASTM A123 in accordance with details shown on referenced drawing 500-2 in Contract HRB-5B (contained in Attachment B) affixed at both ends of the wire rope cut, **installation of zinc buttons in accordance with details shown on referenced drawing 500-6 in Contract HRB-5B (contained in Attachment B).** Estimated number of cuts required = 5 with estimated 10 sockets to be affixed.

**BIDDERS ATTENTION IS CALLED TO:
“REVISED ATTACHMENT A” DATED 11/5/2014**

**DELETE PARAGRAPH 10 IN INS ENTITRY AND REPLACE IT WITH THE
FOLLOWING INSERT:**

10. Quote shall include fabrication of rope, storage of fabricated rope, preparation of rope upon notification from the Authority of the length required (assume maximum of 5 cuts to the fabricated rope will be required), installation of anchor sockets to both ends of the rope **installation of the zinc buttons**, proper handling (wrapped and spooled) and transportation to the location below upon completion of the socket installation within 5 days of notification of length required, to the satisfaction of the Authority.

INSERT THE FOLLOWING AS NEW PARAGRAPHS:

14. At the time the suspender ropes are measured, a paint stripe shall be placed along the length of each suspender rope. A circumferential paint mark shall be made on each suspender rope at the midpoint between sockets to match the centerline at the top of the cable bands. Zinc buttons shall be cast onto each suspender rope to correspond to the location of the suspender clamps.
15. Zinc button installation and procedure qualification shall be based on physical testing. Specimens shall be fabricated from a pre-stretched rope and tested to 6000 pounds. The procedure shall include method of cleaning the rope, temperature of the mold, temperature of the molten zinc, the apparatus for heating and for holding the rope and the mold in place before pouring.
16. Any cracks in the zinc buttons or separations from the rope shall be cause for rejection of the procedure and a new procedure shall be developed and tested until the buttons perform to the satisfaction of the Authority
17. Zinc buttons shall be installed, after suspenders have been proof loaded, in strict adherence to the qualified installation procedure.

**ATTACHMENT B, DRAWINGS,
AS THE THIRD DRAWING:**

**INSERT AS AN ATTACHMENT THE COVER SHEET AND SHEET 500-6
(FROM THE CONTRACT HRB-5B) ENTITLED “SUSPENDER ROPE
CLAMPS”.**

This communication should be initialed by you and annexed to your Bid upon submission.

In case any Bidder fails to conform to these instructions, its Bid will nevertheless be construed as though this communication had been so physically annexed and initialed.

THE PORT AUTHORITY OF NY & NJ

KATHY LESLIE WHELAN
COMMODITIES AND SERVICES DIV
PROCUREMENT DEPARTMENT

BIDDER'S FIRM NAME: _____
INITIALED: _____
DATE: _____

QUESTIONS CONCERNING THIS ADDENDUM MAY BE ADDRESSED TO
LARRY WAXMAN, WHO CAN BE REACHED AT (201) 395-3451 or at
Lwaxman@panynj.gov. addendum #3.

BID 40170
ADDENDUM 3
November 20, 2014

GEORGE WASHINGTON BRIDGE - SUSPENDER ROPE REPLACEMENT

Materials Purchase Order SAP# 10094772

Charge Code: B04-924161

ATTACHMENT B COVER SHEET *M*

DRAWINGS

Sheet 500-2 (from Contract HRB-5B) entitled, "Strand Shoes Suspender Sockets"

Sheet 500-3 (from Contract HRB-5B) entitled, "2-7/8" Dia. Suspender Rope"

→ Sheet 500-6 (from Contract HRB-5B) entitled "Suspender Rope Clamps"

