# **Transportation Management Plan**

# Guidelines



The Port Authority of Traffic Engineering February 2018

## The Port Authority of New York & New Jersey

# THE PORT AUTHORITY OF NY & NJ

# Contents

Α.	PA TMP POLICY	3
В.		4
C.	TMP MEMORANDUM TEMPLATE & INSTRUCTIONS	6
D.	TMP REPORT SCOPING CHECKLIST	8
E.	TMP REPORT TEMPLATE & INSTRUCTIONS	9
F.	TMP REPORT QA/QC CHECKLIST	23
AP	PENDIX A	.24
AP	PENDIX B	27
AP	PENDIX C	.28

# A. PA TMP Policy

### THE PORT AUTHORITY OF NY & NJ

### THE PORT AUTHORITY OF NEW YORK & NEW JERSEY

### PORT AUTHORITY NEWS BULLETIN

#### Offices of the Chief Operating Officer and Chief Engineer

**Bulletin #17-01** 

### DEVELOPMENT AND IMPLEMENTATION OF TRANSPORTATION MANAGEMENT PLANS

This bulletin sets forth an agency-wide, structured approach to developing and implementing Transportation Management Plans (TMPs). A formal policy document is expected to be released shortly. TMPs ensure the safe and efficient movement of people and goods during construction, and minimize impacts to the regional transportation network. Although the Port Authority previously developed and implemented TMPs on a case-by-case basis, the purpose of this bulletin is to ensure there is a documented programmatic and regional approach, which promotes the efficient delivery of infrastructure improvement and enhancement on an ongoing basis. TMPs are now integrated into the project delivery process. TMPs are included in the Project Initiation Request Form (PIRF) and are listed under the "Project Criteria" section in the Engineering Department's project proposal.

TMPs are an industry-standard practice and are developed and implemented by agencies in New York and New Jersey. Additionally, the Federal Highway Administration (FHWA) encourages all agencies to develop and implement TMPs and recognizes TMPs as a "best practice" that will lead to improved community relations and reduced liability.

The Chief Traffic Engineer is responsible for determining if a TMP is required. Project teams will develop and implement TMPs in consultation with all project stakeholders (e.g., internal project stakeholders, other transportation agencies in NY & NJ, police departments, fire departments, emergency services, and communities). TMPs must be developed and implemented prior to the commencement of construction.

TMPs shall consist of one or more of the following components determined by the project characteristics and anticipated transportation impacts:

a) A Traffic Control Plan, which facilitates the safe passage of travelers through a project work zone while maintaining a reasonable level of service, and ensures work zone safety.

b) A Transportation Operations component, which will identify multi-modal strategies to mitigate impacts of construction on the operation and management of transportation systems.

Page 1 of 2

January 26, 2017

Examples of Transportation Operations strategies include demand management, corridor/network management, enforcement, and active traffic management.

c) A comprehensive Public Information component, which will include communication strategies to inform affected travelers, community members, and appropriate public entities about the project, the anticipated transportation impacts and mitigation strategies.

TMPs must be monitored and reported on in real-time and adjusted as necessary through project completion.

Line Department Program Management is responsible for coordination efforts associated with the overall development and implementation of a TMP in consultation with all project stakeholders (e.g., internal project stakeholders, other transportation agencies in NY & NJ, police departments, fire departments, emergency services, and communities). In addition, they are responsible to ensure that a TMP considers on-going and planned construction in the region; this will ensure that transportation management efforts across all modes of transportation within the region are synchronized.

The Port Authority Agency Operations Center (PA-AOC) is responsible for monitoring and reporting on TMPs and making real-time adjustments to TMP strategies in cooperation with facility Operations Control Centers, peer transportation management centers in NY and NJ, and the Transportation Operations Coordination Committee coalition (TRANSCOM) to adjust to changes in project schedules and activities and incidents on the regional transportation network.

Mainer, Dawsn

Stephanie Dawson Chief Operating Officer

### THE PORT AUTHORITY OF NY& NJ

James Starace Chief Engineer

Page 2 of 2

January 26, 2017

# **B.** Introduction

When a construction project will impact traffic within the PANYNJ jurisdiction or beyond PANYNJ facilities, the PANYNJ assesses the impacts, develops strategies to mitigate impacts, and coordinates with internal and external parties affected. This will be accomplished through the development of a Transportation Management Plan (TMP). While many PANYNJ projects have localized impacts on the motoring public within the Port Authority's jurisdiction during the project construction phase, others may involve sister agencies or local facilities, necessitating coordination between agencies and adequate planning of construction projects to mitigate significant impacts on travel times.

The purpose of this guideline document is to provide a standard format and template to aid in the preparation of all PANYNJ TMPs. The TMP guidelines focus on communications protocols, stakeholder coordination, description and assessment of construction impacts, and development, implementation and monitoring of mitigation strategies. The audience includes internal PA stakeholders and external transportation agencies.

The TMP is an on-going process and shall be updated as needed throughout the lifecycle of the project. Additionally, TMPs consist of multiple components including:

- The written document (TMP Memo/Report)
- Communications plans and protocols
- Public outreach prior and throughout construction
- Coordination and meetings with stakeholders from other agencies prior to and throughout construction
- Traffic control plan(s) (Maintenance of Traffic Drawings)
- Implementation of mitigation strategies during construction
- Traffic monitoring and reporting during construction

While considering a TMP for a project, determine whether a TMP Report or a TMP Memo format is required, using the decision tree in Figure B-1 to guide the selection of the appropriate template. Information required includes:

- A review of the project description and other relevant information.
- A review of the Maintenance of Traffic (MOT) drawings and expected traffic impacts associated with the Hours of Work and MOT.
- A determination of the extent of traffic impacts.

The TMP Memo format will be used in most cases, especially for smaller projects whose influence area is contained wholly within the PANYNJ jurisdiction. A few, large projects which impacts traffic beyond PANYNJ jurisdiction will follow the TMP report guideline, unless those impacts can be mitigated solely through MOT and construction staging. A scoping checklist is included in Section C of this document to assist in collecting additional data to complete the TMP report format.

The Project Initiation Request Form (PIRF) is developed by the Project Manager (PM) outlining the scope of work including type of work, schedule, costs, etc. Traffic impacts must be considered throughout the development of the PIRF to determine the need for a TMP. The Engineer of Projects (EOP) prepares the Engineering Department's proposal for the project based on the scope of work outlined in the PIRF and selects whether a TMP is required or not in Project Delivery Proposal System (PDPS). The Lead Engineer/Architect (LE/A) may choose to consult with the Traffic Task Leader regarding this step. At the end of Stage III, the TMP will be submitted by the Traffic Task Leader to the PM with the final design submission of the project. For Design-Build (DB) projects, the Engineer of Record (EOR) shall submit the completed TMP at the end of the Design Phase to the Port Authority Project Manager. The

TMP will then be distributed by the Project Manager to the appropriate stakeholders to be made aware of the mitigation strategies developed for the project, as well as who and how to notify multiple audiences of traffic impacts. The Agency Operations Center (AOC) will monitor the traffic impacts of construction and provide reports as appropriate. This process can be seen in Figure B-2, which shows the TMP Work Flow Diagram.

Any non-italicized text shall be included in your TMP report or Memo. Italicized text is instructional.

This guideline document provides examples of data, performance measures, and mitigation strategies. The engineer preparing the TMP will include applicable sections to document readily available information/analysis on existing conditions, expected impacts, and planned mitigations. Not all items are applicable to every project. However, if the engineer determines that additional analysis is necessary, he or she should request that analysis from the relevant line department as discussed in Section C - Project Description of this document.

The TMP preparer sends the TMP Memo/Report to the Project Manager for distribution to appropriate contacts inside and outside the agency.

Figure B-1: Decision Tree



Figure B-2: TMP Work Flow Diagram



## Transportation Management Plan Guidelines

# **C. TMP Memorandum Template &** Instructions

The following is the layout for a TMP Memo and will be used for most projects, especially for projects whose project influence area is contained entirely within the PANYNJ jurisdiction, as determined in the decision tree (Figure B-1).

The TMP Memo will be completed as a Memorandum from the Traffic EOR to the Project Manager. Each section shall consist of no more than a paragraph or two, with the goal of limiting the memo to 2 pages (see Figure C-1).

## THE PORT AUTHORITY OF NY & NJ

Transportation Management Plan

# MEMORANDUM

- Traffic Engineering
- To: **Project Manager**
- Engineer of Record From:
- Date: Month XX, 201X
- TMP Memorandum PROJECT # and NAME Subject:
- Chief Traffic Engineer, Assistant Chief Traffic Engineer, Traffic Design Principal, Traffic Copy To: Operations Principal, Manager of Agency Operations Center (AOC), Lead Engineer/Architect, Traffic Engineering Task Lead, GOCOR, Media Relations, Marketing

#### Ι. Project Description and Schedule

This section will include a short description (3-4 sentences) about:

- PID and Contract number
- Project scope (roads/facilities involved and improvements to be constructed)
- Project limits ٠
- Purpose/need of the project
- Dates for construction •

### II. Hours of Work Include contract Hours of Work, separated by stage and/or area as appropriate.

III. Maintenance of Traffic/Construction Staging

This section will include a short description and/or graphic about:

- Lane closure information and dates by stage derived from MOT and construction staging drawings (refer to • contract drawings)
- Pertinent detour information

Pedestrian MOT

### **IV. Impacts and Mitigation**

This section will include a summary of traffic impacts expected as a result of the project. Attach any traffic

volumes are very low."

### V. Monitoring

The Agency Operations Center (AOC) will monitor the impacts of construction for any potential disruptions and will issue monitoring reports as required.

Traffic Engineering shall be notified of any changes in the stipulations within this Transportation Management Plan (TMP).

Choose from one of the options below:

Prepared by Consultant for Traffic Engineering; Consultant is Engineer of Record for Traffic Engineering on subject project.; or

Prepared by Port Authority Traffic Engineering.

Firm name should be updated where applicable.

# analysis performed for this project. If the example below cannot be applied to a project, consider TMP Report.

• Summary of traffic impacts and mitigation strategies – for example, "The traffic impacts are minimized by staging construction to be performed in routine single lane closures during nights and weekends," or "Traffic impacts are expected to be minimal because work will take place during weekend hours when the traffic

Figure C-1: Sample TMP Memo

THE PORT	AUTHORITY	OF NY& N
----------	-----------	----------

### MEMORANDUM

Traffic Engineering

Transportation Management Plan

- To: Aviva Oppenheim (Project Manager)
- From: William Bothe (AECOM Engineer of Record)
- Date: September 07, 2017

Subject: TMP Memorandum - PABT BT-200.300 W.O.#30 - Remove VTU

Copy To: J. Rivera, M. Baig, M. Diculescu, T. Bobowsky, A. Lepore, A. Rawashdeh, A. Levi, J. Bernbach, T. Lado, R. Marsico, A. Mancher

### I. Project Description and Schedule

The primary objective of this contract (PID# 17682000, BT-200.300 WO#30) is to demolish the existing Video Teleconferencing Unit (VTU) area walls, doors, column finishes, and the lower level floor slab and existing foundation in the vicinity to provide space for a future proposed escalator. Work is primarily in the pedestrian access corridor and escalator area adjacent to the lower level bus gate access road. The construction duration is anticipated to be six (6) months and is scheduled to begin November 2017.

#### II. Hours of Work

- Hours of the South Wing south side bus gate closure, south side bus gate access lane closure, and restricted lane width on north side bus gate access lane are 1AM to 5AM.
- Restricted lane width of the bus gate access lane and closure of four (4) bus gates will occur during the daytime.

#### III. Maintenance of Traffic/Construction Staging

The work associated with this project will be performed with closures of the lower level South Wing south side bus gates and adjacent bus gate access lane, as well as restricted lane widths on the lower level South Wing north side bus gate access road. Detours will not be required for the lane closures.

Construction staging is as follows:

- Nighttime Closure Lower level South Wing south side bus gate closure and bus gate access lane closure. Also, restricted lane width on South Wing north side bus gate access lane and single bus gate closure (contract drawing MT2102).
- Daytime Closure Lower level South Wing bus gate access lane width restriction and partial bus gate closure (contract drawing MT2103).

#### IV. Impacts and Mitigation

Traffic impacts are expected to be minimal because bus gate and access lane closure will take place during the night time hours between 1AM and 5AM when traffic volume is

## MEMORANDUM

very low and South Wing bus gates are not in use. In addition, the impacted roadways are restricted bus access roads with no access to public traffic. Only bus traffic entering the terminal to serve the lower level gates will be impacted. Buses will continue to use the outside bus gate bypass lane road to access the operating gates on north side of the work area or in the North Wing.

#### V. Monitoring

Since all impacted traffic is within the PABT, the Agency Operations Center (AOC) monitoring is not required for this project.

Traffic Engineering shall be notified of any changes in the stipulations within this Transportation Management Plan (TMP).

Prepared by AECOM for Traffic Engineering; AECOM is the Engineer of Record for Traffic Engineering on subject project.

### THE PORT AUTHORITY OF NY& NJ

Page 2

# **D. TMP Report Scoping Checklist**

The scoping checklist provided below outlines the basic steps and documents needed to complete a TMP Report. Every item is not required, the TMP preparer and the LE/A should coordinate to determine necessary steps. The following is a guide, some projects may require additional information/tasks and some fewer.

A. Project Description		Data Collected (Y/N/NA)	Comments
A1.	Gather the project description and other relevant information		
A2.	Review MOT drawings		
A3.	Determine project limits with LE/A		
A4.	Create study area map		
A5.	Collect relevant traffic and transportation conditions from previous studies (i.e. Stage I or Stage II reports)		
A6.	Review Environmental Assessment (EA) or Finding of No Significant Impact (FONSI) if applicable		
A7.	Document project alternatives that were considered and why the Preliminary Preferred Alternative (PPA) was chosen (LE/A)		
A8.	Determine areas for local and regional influence/impact		
A9.	If relevant information is missing, request additional information/data on local and regional impact areas from departments listed		
A10.	Collect information on regional construction projects that could have impact on the TMP project area (Project name, owner, schedule) and qualitatively assess potential impacts		
A11.	Define Task Force Members		
A12.	Meet with Task Force to: – Review A1A10. – Brainstorm mitigation strategies		
A13.	Gather additional information to complete Chapter 1 of the TMP report (see Section D of this document)		

B. Im	pacts and Mitigation	D		
B1.	Review available MOT drawings, Hours of Work and construction schedule			
B2.	Assess impacts of MOT on local and regional facilities specific to high crash locations, volumes, LOS, queues, delays, transit impacts, aviation or maritime impacts			
ВЗ.	Develop mitigation strategies and determine which construction stages require Traffic Mitigation & Communication Plans (TMCP) in conjunction with the AOC. Develop TMCPs			
В4.	<ul> <li>Meet with Task Force</li> <li>Review B1. And B2.</li> <li>Determine roles and responsibilities for strategy implementation</li> <li>Brainstorm monitoring and performance metrics</li> </ul>			
в5.	Gather additional information to complete Chapter 2 of the TMP report (see section D of TMP Guidelines)			
C. Coordination and Monitoring				
C1.	Determine roles, responsibilities, and schedule for regional project coordination			
C2	Develop outreach plan and define responsibilities			
C3.	Develop project specific Incident Management flow chart			
C4.	Develop monitoring plan			

Data Collected (Y/N/NA)	Comments
Data Collected (Y/N/NA)	Comments

# E. TMP Report Template & Instructions

The following sections depict the layout and describe the content for a TMP Report.

The document will be arranged to minimize white space while maintaining continuity of information. Some sections may follow a two column format to allow maximum text per page and ease of reading, while others will be formatted in a three column format allowing for larger graphics to use two thirds of the page.

The report cover should match the cover of this document. Cover photos will be replaced with project specific photos, but fonts and layout will remain the same. On the cover, the word "Guidelines" shall be replaced with FAC-XXX.XXX Project Title. The cover will also state "Prepared for Traffic Engineering by FIRM", with the word 'FIRM' to be replaced with the Consulting Firm's name. The Table of Contents will also match the table of contents of this document as shown on the next page. A list of acronyms and abbreviations should match those shown on following pages. These lists are not all inclusive and should be updated to include additional relevant acronyms or abbreviations. Appendix A includes the style guide that the TMP preparer will use to match the layout, fonts and colors for the document. Colors, chapter titles, fonts and sections are not to be modified without input from PANYNJ Traffic Engineering.

# **TMP Report Table of Contents**

ACRONYMS AND ABBREVIATIONS	11
EXECUTIVE SUMMARY	12
1 PROJECT DESCRIPTION AND SCOPE	13
1.1 Project Description	13
1.2 Project Area	13
<b>1.3 Existing Conditions</b> 1.3.1 Traffic         1.3.2 Transit         1.3.3 Aviation         1.3.4 Marine Ports	<b>13</b> 13 13 13 13 13 13
1.4 Project Alternatives	<b>13</b>
1.4.2 Preliminary Preferred Alternative	13
1.5 Task Force	14
1.6 Environmental Assessment and Finding of No Significant Impact (FONSI)/Record	of Decision (ROD)14
1.7 Regional Projects	15
2 IMPACTS AND MITIGATION	16
2.1 Construction Stages & Hours of Work 2.1.1 Potential Traffic Impacts	<b>16</b> 16
2.2 Mitigation Strategies	16
3 COORDINATION AND MONITORING	18
3.1 Outreach	18
3.2 Incident Management	19
3.3 Monitoring and Reporting	

# **List of Figures**

# **List of Tables**

Table 1-1: Explored Alternatives
Table 1-2: Internal Task Force Members
Table 1-3: Partner Agency Task Force Members
Table 1-4: Regional Projects
Table 2-1: Hours of Work and Traffic Impacts
Table 2-2: Implementation Strategy Category
Table 3-1: Outreach Plan

## Transportation Management Plan Guidelines

	19
	20
	21
	22
	22
	26
t	27

15	 
16	 
17	 
18	 •••
10	 •••

# **Acronyms and Abbreviations**

Below is list of acronyms and abbreviations that may be used in this TMP report. ADT – Annual Daily Traffic AADT - Average Annual Daily Traffic **AOC - Agency Operations Center** ATR - Automated Traffic Recorder **CMD** - Construction Management Division EA - Environmental Assessment FAA - Federal Aviation Administration FHWA - Federal Highway Administration FONSI - Finding of No Significant Impact **GOCOR - Government and Community Relations** GWB - George Washington Bridge **ITS - Intelligent Transportation Systems** JTMC - Joint Traffic Management Center

LE/A – Lead Engineer/Architect

LOS - Level of Service

MOT - Maintenance of Traffic

MPO - Metropolitan Planning Organization

- MTA Metropolitan Transportation Authority
- NB-HCE Newark Bay Hudson County Extension
- NJDOT New Jersey Department of Transportation
- NJTA New Jersey Turnpike Authority

NJTPA - North Jersey Transportation Planning Authority

- NYCDOT New York City Department of Transportation
- NYMTC New York Metropolitan Transportation Council
- NYSDOT New York State Department of Transportation
- **OCC Operations Control Center**

O-D - Origin-Destination

**OEM - Office of Emergency Management** PANYNJ - Port Authority of New York and New Jersey PATCO - Port Authority Transit Corporation PATH - Port Authority Trans-Hudson **PID - Project Identification Number PIP - Palisades Interstate Parkway PIRF - Project Initiation Request Form** PM - Project Manager **PPA - Preliminary Preferred Alternative ROD** - Record of Decision **RPO - Regional Planning Organization** SSP - Safety Service Patrols **TDM - Travel Demand Management TEA - Traffic Enforcement Agents TEU - Twenty Foot Equivalent Unit TIP - Transportation Improvement Program** TMC - Turning Movement Counts TMP – Transportation Management Plan **TRANSCOM - Transportation Operations Coordinating Committee** VMS - Variable Message Sign XBL - Express Bus Lane

Page | 11

# **Executive Summary**

The executive summary will include a brief description of the project and the expected impact areas due to project construction. A succinct explanation of the preferred alternative shall include bullet points outlining the scope, schedule, and duration. The following excerpt is from the GWB-244.150 TMP Report.

The Replacement of Palisades Interstate Parkway (PIP) Helix and Rehabilitation of Upper Level Spans over New Jersey Anchorage and Hudson Terrace project will extend the life of this connector by completing roadway repairs and replacement of the three bridges along the PIP Helix. The finished project will meet applicable codes for seismic capacity.

The preferred alternative calls for full rehabilitation including replacement of the existing PIP helix ramp on the current alignment with traffic detoured onto a new temporary detour roadway, requiring complex staging. This Transportation Management Plan (TMP) lays out the construction conditions, effects on traffic delays and mitigation strategies to successfully manage traffic and congestion during construction.

- Project scope includes:
  - Demolishing the existing bridges
  - $\circ$   $\;$  Erecting a temporary helix roadway and bridges  $\;$
  - o Constructing the new permanent helix roadway
  - $\circ$   $\;$  Demolishing the temporary helix roadway and bridges  $\;$
- Anticipated construction cost is \$69.87 million (2015).
- Scheduled to start in July 2016 and finish in October 2019 with an overall duration of 27 months (including winter months where construction is suspended).
- Impact areas include:
  - Local streets in Fort Lee, NJ
  - Regional roadways in northern New Jersey
  - Downstate New York
  - o New York City

Transportation Management Plan Guidelines

## 1 **Project Description and Scope**

## **Project Description** 1.1

This section will include a short description of roads/facilities involved and improvements to be constructed. The description must include a clear and concise declaration of the project, explain context, goals and objectives and state the project need and problem to be addressed.

## 1.2 **Project Area**

The Project Area shall be defined by the project limits and must also include areas where impacts are anticipated. This section will include one or more graphics that show local and regional areas of influence. This section should list roadways and facilities in the immediate vicinity of the project as well as regional roadways and facilities with anticipated traffic impacts due to the project construction. Roadways are to be described in terms of number of lanes, access, and type of control (i.e. Road A is a two lane local route with stop controlled and signalized intersections).

### 1.3 **Existing Conditions**

Describe the existing traffic conditions (including all modes that may be impacted) in the project area that may be impacted by the project.

This section will provide a context of the prevailing traffic conditions of the study area. Depending on the scale of the project and projected impacts, the Project Manager and Traffic Engineering Task Lead will determine which traffic analyses will be required. Descriptions of the potential traffic analyses are briefly described below. Data, analyses and results will be presented by subject area (i.e. Traffic, Transit, Aviation, Cargo, Safety, etc.).

Descriptions can be accompanied by graphics displaying the results on maps or charts.

All relevant traffic and transportation conditions from previous studies (i.e. Stage I or Stage II reports, etc.) will be summarized and discussed in this section. Full reports and analyses shall be referenced and may be included as appendices. If previous studies are not available, data required to describe the existing traffic conditions may be collected to establish a baseline condition.

### **Traffic** 1.3.1

Existing traffic conditions are to be briefly described. This should include observed parameters (i.e. queues, LOS, volumes, etc.) for roadways, intersections and/or facilities in the project area. Include full details under appendices for more detailed information. Traffic data could include but not be limited to volumes, speeds, travel times, Level of Service (LOS), Origin-Destination survey, crash history, and/or bicycle and pedestrian data.

#### 1.3.2Transit

Transit conditions (for bus, rail, terminals, depots, ferries or other facilities) will be described if there are anticipated impacts on transit routes, ridership, headways, etc. or if they are to be utilized as part of the mitigation strategies.

Include full details under appendices for more detailed information. Transit data could include, but not be limited to ridership, headways, frequency, passenger loads, or origin-destination data.

### 1.3.3 Aviation

Existing aviation conditions will be described if the project impacts landside operations. Include full details under appendices for more detailed information as appropriate. Aviation data could include, but not be limited to passenger traffic, load factor, frontage stops and dwell times, parking, air-train usage, bus and/or taxi ridership.

### 1.3.4 Marine Ports

If a marine terminal project is expected to impact traffic on the surrounding roadways, this section shall briefly describe existing Marine Port conditions analysis. Include full details under appendices for more detailed information. Port data could include, but not be limited to, marine traffic (arrivals/departures), container port traffic, internal container port traffic, or vehicular access traffic.

## 1.4 **Project Alternatives**

In this section, the project alternatives previously studied will be summarized and the preferred alternative will be discussed in more detail. The purpose of this section is to describe the multiple possibilities/outcomes that were considered and why the Preliminary Preferred Alternative (PPA) was selected.

### 1.4.1 **Explored Non-Selected Alternatives**

A table (similar to Table 1-1) will include a brief description of each alternative that was considered and why each was rejected prior to the selection of the PPA. If needed, graphics of the alternatives can be included.

### 1.4.2 **Preliminary Preferred Alternative**

The PPA will be described in greater detail including a graphic and why it was chosen. A brief discussion of how the alternative will be implemented shall be included.

Table 1-1: Explored Alternatives

	Description	Ī
1	Briefly describe the alternative including cost, duration, and impacts as necessary.	
2	Continue table as necessary to include all investigated alternatives and the corresponding reasons for elimination.	

Reason Eliminated

Briefly explain reason not chosen due to cost, duration, not meeting purpose and need, etc.

# 1.5 Task Force

This section identifies the responsible parties for coordination and communication internal to the PANYNJ as well as externally with other agency partners. The Task Force shall be engaged early in the TMP development to help guide strategy selection, and later be involved in the day-to-day implementation of the plan. It is not intended that each member will take part in all activities; rather the PANYNJ Project Manager will determine which members are needed for specific tasks or meetings. For example, the entire Task Force (internal and external) might be convened during Stage 2 to gather information from all impacted agencies/organizations, but during strategy selection, a smaller group may be convened, i.e., such as the internal group plus NJ Transit for any strategies involving public transit.

Each member group shall have a representative for regular communications with contact information in a table. This section will denote contacts for specific activities which occur on a recurrent basis, such as materials delivery, late lane reopening, etc. Example tables are shown for internal members (Table 1-2) and external members (Table 1-3). These tables are not meant to be exhaustive and can be modified as needed for the project. Delete inapplicable rows.

### Table 1-2: Internal Task Force Members

Group	Contact	Phone Number	Email
PANYNJ Project Manager			
PANYNJ Traffic Engineering			
PANYNJ AOC			
Facility			
Facility OCC			
Construction Management Division (CMD)			
PANYNJ Police			
PANYNJ Marketing			
PANYNJ Media Relations			
GOCOR			

### Table 1-3: Partner Agency Task Force Members

Organization	Contact	Phone Number	Email
NYCDOT			
NYSDOT			
NJDOT			
NJTA			
Transit Agencies			
State/Municipal OEM			
TRANSCOM			
Contractor			
County/Municipal Representative			
MPO/RPO			

# 1.6 Environmental Assessment and Finding of No Significant Impact (FONSI)/Record of Decision (ROD)

If applicable, this section will include a paragraph summary of environmental document findings, with a reference to where the full documents can be found, or attached as appendices. If not applicable, then delete this section from the TMP report.

# **1.7 Regional Projects**

In coordination with the AOC and Traffic Task Lead, the TMP preparer will develop a list of regional projects in close proximity that will be in construction concurrently with the subject project. This list must be incorporated into a bar chart (see table 1-4) depicting the start and end date of each project with the subject project being depicted as a different color so as to clearly illustrate where overlaps exist. The TMP preparer will include a narrative explaining the interdependency between the projects regarding the potential conflicts that can arise from having these projects run concurrently.

The PANYNJ Project Manager will coordinate with other projects identified in this section (within PANYNJ or other agencies) regarding lane closures or other impacts to minimize impacts to the regional transportation network. Impacts include detours and diversions that might pass through or close to the impact area of the project. Project managers should coordinate with the Facility, Traffic Engineering, Construction Management (CMD), and the AOC to understand potential impacts and to develop mitigation strategies as needed.

Each coordination effort only captures a specific moment in time – schedules change for a number of reasons (i.e., funding, other project, other agency, or local priorities). If there are "volatile" (schedule in flux) projects on the list, the PANYNJ project manager should coordinate with those agency project managers more frequently.

Impacts of major regional special events (i.e., sporting events, parades, festivals, etc.) must also be considered in regional construction and lane closure coordination. Some of these events will contain road closures that could affect access and egress to Port Authority facilities.

	Major Regional Construction Projects																									
		20	017			2	2018			2	019			20	020		2021				2022					
	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	0
Suspender Ropes Replacement and Main Cables Rehablitation																										
NIDOT						_							_													
Pulaski Skyway Payement Rehabilitation Project (Contract 2)						-	-					-	-													
Fulaski skyway Favement Kenabintation Floject (Contract 2)							-	_																		
Route 7 Hackensack River (Wittpenn) Bridge - Contract 3 of 4																										-
																										-
I-495, RT 1&9 / Paterson Plank Road Bridge																										
PANYNJ																										
Bayonne Bridge																										_
																										_
PIP Replacement																										
CWR Encility Wide Driverty Republication																										
GWB Facility wide Frionty Kenabilitation							-	_																		
Rehabilitation of Center and Lemoine Avenue Bridges																										1
																										1
Rehabilitation of Ramp 178/179, Bus Ramps and Bus Turnaround																										/
Trans-Manhattan Expwy Median Barrier Replacement																										
Phase 2 Structural Steel Repair																										4
the sector of Freedow and Maria Cases Devices on Data billion to a																										
Upper Level Eastbound Main Span Pavement Renabilitation																										
Trans Manhattan Water Line Bland C																										
NJTA																										-
TPK Pavement Resurfacing (Annual Program)																										-
Interchange 14A																										
Bridge Deck Replacement (NBHCE)																									1	

### Table 1-4: Regional Projects



Page | 15

## 2 Impacts and Mitigation

## **Construction Stages & Hours of Work** 2.1

This section will be presented as tables or text to provide an explanation of stages and impacts in a clear, concise manner. The table or text will include the stage number, description of anticipated closures, an indication of which hours of work are impacted, the duration of closures, and expected delays. A sample table is shown in Table 2-1. Additional columns can be added to show expected delays in other seasons, if applicable.

Table 2-1: Hours of Work and Traffic Impacts

Construction Stage	Lane Closures	Hours of Work	Hours	Unmitigated Delays (minutes)	Mitigated Delays (minutes)
В	Lower Level Westbound, PIP Southbound, Right shoulder of Upper departure (Lane 5-7)	Sat/Sun 9:00 PM - 11:00 AM	14	20-35	10-12
C-D	Ramp TR1, Ramp TR2	Sat/Sun 11:00 PM - 9:00 AM	10	20-35	5-10
E	Lower Level Eastbound, PIP Southbound, Ramp TR2, Ramp TR4	Sat/Sun 9:00 PM - 11:00 AM	14	30-45	10-15
	Three (3) east toll lanes (Lanes 34, 36 and 38) of PIP Toll Plaza	Sat/Sun 6:00 PM - 11:59 AM	18	10-15	5-10

### 2.1.1 **Potential Traffic Impacts**

For any construction stage that has more complex traffic impacts, a text description beyond Table 2-1 may be required. This shall include a short description (and/or table and/or graphic) depicting anticipated impacts without mitigation beyond MOT or Hours of Work put in place. This includes disruptions to traffic, transit, and other facilities such as roadways, toll plazas, bridges, tunnels, aero and marine terminals, parking, and ITS infrastructure. Impacts might be local and/or regional. Consideration should be given to impacts to other regional projects that will be under construction concurrently.

If applicable, impacted conditions traffic analysis will be briefly described, following the content provided in Section 1.3 above. Projected parameters for roadways, intersections and/or facilities in the project area are to be provided below. Include full details under appendices for more detailed information.

The TMP preparer must obtain baseline travel times where available and record in areas without monitoring devices prior to the beginning of construction. Manual travel time collection during construction may also be considered. Coordinate with the AOC to determine data needs and the ITS and planning groups for data availability.

## 2.2 **Mitigation Strategies**

Mitigation strategies that will be implemented to alleviate impacts will be defined. Factors to be considered when selecting viable strategies include cost, expected benefit, and ability to implement within the time frame needed, operational aspects, impacts, and other considerations.

This section will include a table of all strategies that were considered and justifications for any eliminations, as well as expanded descriptions of the strategies that are recommended for implementation.

Strategies shall be grouped into categories that will include topics such as traffic control/operations, transit and travel demand management, construction/contracting, incident management, and outreach. There may be some strategies that are only in place for one or two stages of construction or for only one or two program projects. This will be indicated in the text, specifically referring to the stage and schedule for that strategy.

This section will include a table for each strategy category showing roles and responsibilities for each of the proposed mitigation strategies, as well as the method of implementation to be utilized. A sample table is shown in Table 2-2.

Some example strategies to be considered in these tables (include but are not limited to):

### **1.** Traffic Control Plan

- lanes, Hours of Work, traffic screens, etc.
- additional lane capacity, managed lanes, adaptive signal control, etc.
- completion and penalize schedule overruns.

## 2. Transportation Operations Strategies

- a) Ridesharing includes forming and/or subsidizing carpools, vanpools, etc.
- b) Employer programs includes telecommuting and flextime programs
- c) New/enhanced rail service can include additional seating, additional train trips, etc.
- routes, etc.
- e) PATH includes decreased headways
- f) Ferry includes increased frequency on existing routes or new service

a) Protocols for lane closures/staging - includes reduced lane widths, lane/shoulder closures, reversible

b) Capacity increases – this includes spot intersection improvements, signal timing/phasing changes, c) Traffic detours/restrictions – includes signing well in advance of detour location, turn restrictions, etc. d) Incentive/disincentive clauses – includes clauses written into contractor's contract to incentivize early

d) New/enhanced bus service – can include new bus routes, increased capacity or frequency on exiting

g) Park and Ride – includes new lots, increased transit service to existing lots, etc.	Table	2-2: Implementation Strateg	gy Category				
<ul> <li>h) Taxi/For-Hire Vehicles (FHV)</li> <li>i) Incident detection – includes traffic cameras, Intelligent Transportation Systems (ITS) devices, increased patrols, etc.</li> <li>j) Incident response – includes continued access for emergency responders, towing service, improved</li> </ul>	#	Operational Scenario	Impacted Roadways and/or Intersections		Mitigation Strategy	Applicable Construction Stage	Responsible Entity
<ul> <li>Inclaent location/markers, etc.</li> <li>k) Motorist information – includes Variable Message Signs (VMS) with incident information at key commuter decision points, traffic radio reports, Waze, 511.</li> <li><b>3. Public Information Strategies</b> <ul> <li>a) Electronic information - includes project website, use of existing email lists, etc.</li> <li>b) Social media –includes Facebook pages and Twitter accounts to disseminate information</li> </ul> </li> </ul>		Single and multiple lane closures on I-95 during standard hours for pier repairs, footing strengthening, rock anchors, and temporary shielding	Upper and lower level departure and approach	•	Increased monitoring in AOC Use electronic and social media to convey construction information	N/A; must be completed during substructure work	PANYNJ
<ul> <li>c) Meetings – includes internal, stakeholder/business owner, kiosks, and public information center</li> <li>d) Print materials, broadcast media – includes flyers, press releases, radio and TV spots, radio traffic reports, etc.</li> <li>e) Hotlines including Waze, 511, etc.</li> <li>f) Motorist information – includes VMS with travel time, detour, and incident information, etc.</li> <li>For a full list of potential strategies, see Appendix C, which has been adapted from Section 4 (Work Zone Impact</li> </ul>	2	Extended 54-hour weekend left lane closures for I-95 for pier reconstruction and guiderail removal/installation	Upper and lower level departure and approach	•	Increased monitoring in AOC Use electronic and social media to convey construction information	N/A; must be completed during substructure work	PANYNJ
Management Strategies) of the FHWA TMP Template at <a href="http://www.ops.fhwa.dot.gov/wz/resources/final_rule/tmp_examples/sample_tmps/sec_c.htm#4">http://www.ops.fhwa.dot.gov/wz/resources/final_rule/tmp_examples/sample_tmps/sec_c.htm#4</a> .	3	Permit left turn from Bruce Reynolds Boulevard to Park Avenue (currently restricted)	Bruce Reynolds Boulevard	•	Cover existing signs Traffic enforcement agents (TEA) at intersection	Center Avenue Stage 1B (AM peak hours only)	PANYNJ
			Center Avenue	•	TEA at critical intersections to assist detoured traffic Modify pavement markings on approach	All Center Avenue Stages	PANYNJ, Fort Lee
	4	Center Avenue Topside Closures and Associated Detours	Bruce Reynolds Boulevard	•	Modify pavement markings between Center Avenue and Hoyt Avenue to reassign lane usage Modify traffic signal timing and/or alter cycle length TEA at critical intersections to assist detoured traffic	All Center Avenue Stages; pavement markings are modified prior to Center Avenue Stages 1A, 1B, and 2A; impacted traffic signal timing modifications vary depending on stage	PANYNJ, Fort Lee, Bergen County, NJDOT
			Center Ramp 4	•	Widen Center Ramp 4 to accommodate two lanes	Prior to Center Avenue Stage 1A and remains a permanent feature	PANYNJ
			Local 1 Ramp at Bridge Plaza North	•	Modify pavement markings Relocate Stop sign to Bridge Plaza North approach	Prior to Center Avenue Stage 1A and remains throughout construction	PANYNJ

# **3** Coordination and Monitoring

# 3.1 Outreach

This section provides a description of how the Public Outreach strategies identified in section 2.2 will be used to inform travelers through such avenues as public meetings, print and TV/radio media, website, social media and hotlines. This will include a matrix of responsible parties for communication and outreach.

In Table 3-1, the 'Audience' describes the user groups being targeted, the 'Distribution Channel' describes the outreach method for reaching that group, the 'Owner' shows whose role it is to reach out to each group, and 'Messaging Information' shows what these groups should be told. When possible, a timeline for this outreach will be included.

Representatives from each affected municipality are to be included in the Outreach Plan. A full list of representatives within five miles of each Port Authority Facility can be found in Appendix B as part of proposed legislation. Agency stakeholder owners have the responsibility to update the list. When completing the TMP report, this list should be updated with current representatives for the facility for the subject project.

Include the following text in every report:

The AOC shall act as a liaison between the outreach and the Task Force for day to day operations. The Project Manager shall act as a liaison to the Task Force to provide project specific information.

Audience	Distribution Channel	Owner	Construction Stage	Messaging Information
Travelers (customers)	511, Navigation Apps, Variable Message Signs, PA Alerts	AOC	В	UL congested, use LL or alt route
(customers)	Printed Material, Website, Radio Spots, Twitter	Public Affairs	B, E	LL closed, use UL or alt route
Partner Transportation Agencies	Meetings, Closure Notification Emails, Real-Time Coordination between Transportation Management Centers	AOC	All Stages	Effects on other agencies roadways due to ongoing construction
Civic and Community Groups (business community, special interest groups, etc.)	Meetings, Advisories	Public Affairs	Entire project	Construction from 2017-2020
Elected Officials (county & municipal)	Meetings, Advisories	Public Affairs	Entire project	Construction from 2017-2020
General Public	Print Media, Press Releases	Public Affairs	C-D	Delays in NJ Local Approach to GWB

### Figure 3-1: Incident Management Protocols

# 3.2 Incident Management

The preparer should coordinate with the AOC to confirm the flow chart and text of this section.

Figure 3-1 depicts the flowchart of the protocol that will be used for incident detection, communication and management. This flow chart will be reviewed and updated by the AOC representative on the Task Force for the TMP.

This section outlines how incidents are identified and responded to. The flowchart summarizes the protocol that is to be followed when an incident occurs. It includes information about how emergency responders are to be notified and how the incident's impacts will be disseminated to regional travelers.

Individual agencies are responsible for reporting incidents in the regional OpenReach (maintained by TRANSCOM) database. This resource is used to feed the live alerts page on the 511 website. In most cases it will be the responsibility of the facility Operations Control Center (OCC) to monitor for incidents on any PANYNJ facility and, together with the Port Authority Agency Operations Center (AOC), oversee response and disseminate information.

Information sharing to the driving public is also critical in the event of an incident. The PANYNJ AOC will be responsible for coordinating internally and externally as appropriate to provide real time travel information via multiple channels.



Page | 19

# 3.3 Monitoring and Reporting

This section provides a short description of metrics to be collected and methods to display/convey the information to evaluate the effectiveness of the strategies chosen.

The TMP is a "living" process that is to be updated throughout construction to track the effectiveness of the mitigation strategies and allow for in-stream adjustments to those measures should it become necessary. Monitoring reports and changes to hours of work or other mitigation strategies will be documented and compiled in project TMP's website. Coordinate with the AOC for website.

This section will outline the reporting intervals (daily, weekly, monthly, etc.) and explain what performance metrics will be collected/evaluated and give a standard method/format for reporting. Performance metrics aim to measure the success of the selected mitigation strategies. As such, performance metrics should be selected based on the mitigation measures recommended in Section 2.2. These measures will vary depending upon the type of project, impacts and facilities impacted.

Generally, the primary metric will be travel times from various points in the study area. The TMP preparer shall work with the AOC to identify locations for travel time monitoring. Other potential performance metrics include Traffic Volumes (by vehicle class where applicable), Intersection and Roadway Delays, Speeds, Incident Rates and Trends, Level of Service (LOS) (i.e. intersection, roadway, frontage, bus service, etc.), Parking Utilization, Dwell Times, Transit Ridership, Gate Hours, Cargo Volumes, etc.

Monitoring should include tracking the selected metrics (typically travel times) during hours of work and in the "shoulder" hours just before and after construction begins and ends. The monitoring will help to determine whether changes to hours of work or other implemented strategies are necessary (including adding new strategies or eliminating ineffective ones).

The TMP preparer will coordinate among the various Traffic Engineering groups to develop monitoring reports. See Figure BB-1 in Appendix B for the Traffic Engineering organizational structure. The workflow structure to determine the trips to be monitored report is as follows and is shown in Figure 3-2:

- (1) The AOC and Design group, with input from the designer/TMP developer, would agree on which MT set-ups/phases would be appropriate to provide reports on. This conversation should be led by the designer and supported with previously conducted impact analysis.
- (2) The designer/TMP developer would produce the attached with suggested trips and start and end points
- (3) The AOC and Design group would have conceptual input into these trips and start/end points

(4) The ITS group would refine the proposed trips to best align with existing trips, deployed sensors, and known data quality issues.

- a. Some trips would be confirmed
- b. Some trips would be modified, such as their starting and ending points, but generally align with what was suggested
- c. Some trips would be identified as lacking data and requiring additional hardware to monitor.
- (5) Add a map showing the identified monitoring locations that lack visibility and/or travel time data (see Figure 3-3).
- (6) AOC, Design and ITS would finalize the content of the monitoring report.

Figures 3-4 & 3-5 depict sample daily monitoring reports for a typical TMP. The creation of the daily report will drive the collection of data along key routes to/from and across the construction area. This report will be used to track the impact of construction on the surrounding roadways.

Monitoring reports are not always project specific, but can combine multiple projects' lane closures and travel times into one report. Currently, for GWB, there is an overnight report that details all lane closures and associated travel times, as well as a comprehensive daytime report, which is also being developed. This reporting strategy may also be applied to other facilities, which may render the need to identify trips to monitor unnecessary.

The AOC and the Task Force will review the daily monitoring reports to assess whether any adjustments are required to the mitigation strategies. The TMP preparer must also produce a write-up for this section to describe the information being provided in each of the figures.

Figure 3-2: Workflow Structure for Trips to be Monitored

Design Maintenance of Traffic Drawings (MOT)
Analyze MOT scenarios that have non-standard configurations and/or hours of work
Compile expected traffic impacts of all MOT scenarios
Identify trips to be monitored
Coordinate with AOC for data availability
If data is missing, coordinate with ITS group to develop a device deployment plan

### Figure 3-3: Areas Lacking Visibility and/or Travel Time



### Figure 3-4: Sample Airport Monitoring Report

### Figure 3-5: Sample GWB Monitoring Report











Page | 22

# F. TMP Report QA/QC Checklist

As a final check that all relevant information is included in the TMP report, the EOR shall complete the checklist during the design of this project and included with TMP submission. This checklist is not to be included in the report.

# Transportation Management Plan QA/QC Checklist

			Engineering Department
		Date:	
Facility:		Projec	ct Manager:
Contract N	Number:	Lead	Engineer/Architect:
PID Numb	per:	Traffic	c Engineering Task Lead:
The follo	owing is a guide, some project	ts may red	quire additional information/tasks and some less
A - TMP	Document	Y   N   n/a	Comments
A1.	Project description and scope		
A2.	Regional Projects		
A3.	Hours of Work Established for all Stages		
A4.	Construction Staging/Sequencing/Scheduling and Associated Traffic Impacts		
A5.	Mitigation Strategies		
A6.	Regional Construction Project Identification		
A7.	Outreach Plan		
A8.	Incident Management Protocol		

В-\$	Stakeholder Identification	Y   N   n/a
B1.	Affected neighboring agencies	
B2.	PA Public Affairs Point of Contacts (GOCOR and Marketing & Media Relations)	
B3.	Affected Port Authority Facility Point of Contact(s)	
B4.	Representatives for Elected officials	
B5.	Civic and community groups	
B6.	Affected local businesses	
B7.	Other stakeholders not identified above	
C - I	Notifications	Y   N   n/a
C1.	Public awareness and traveler information strategies	
C2.	Other types of media that may be explored to inform travelers of construction activity	
D - 0	Coordination	Y   N   n/a
D1.	Internal Task Force members identified	
D2.	Partner Agency Task Force members identified	
E - 1	Monitoring and Reporting	Y   N   n/a
E1.	TMP monitoring metrics and reporting frequency established	
E2.	Traffic monitoring report template established	

Comments

Comments - List person(s) or group(s)
Comments - List strategies
Comments
Comments



# **Color Template**

- **Medium Grey**
- **Medium Grey**

## 1 Heading

### 1.1 **Sub Heading**

#### 1.1 **Sub-Sub Heading**

#### **Sub-Sub-Sub Heading** 1.1.1

Int. At reium, optatem porumque conseque sandisit acillor emporib ustrum restiae porerorio to volesti conem ut

## **Bullets Style**

- placcum quae evel ipsaeptatis dolor am adi vent ese nbvvbnvn hgfhfdgyhfdtg retwetwert yuyuiytitityiyti
- placcum quae evel ipsaeptatis dolor am adi vent ese nbvvbnvn hgfhfdgyhfdtg retwetwert yuyuiytitityiytivbghgfghfhgffff
- placcum quae evel ipsaeptatis dolor am adi vent ese nbvvbnvn hgfhfdgyhfdtg retwetwert yuyuiytitityiytivbghgfghfhgffff

# Graphic Placeholder: 0.125 inch text wrap

Graphic Placeholder: 0.125 inch text wrap

Graphic Placeholder: 0.125 inch text wrap

Figure AA-1 - Sample Impact Area Map

Num quis volor re quamus ditiis di unt omniate et vita dolum ipsae. Et ium fugiae videsse nimusap erepre venisque omnissimus digendunt fuga. Nam nobitatessit qui volupta ini occum delit iumet quiandem nonsegue comnimi liguate cature volupti orrumetum dio. Beat incturis dicillatum fugiam accus rem qui od quuntisquia quassit atatus. faccust ibusdan delicipsam doluptatur? Quia eat volles alibus ea alis eum sinusam volorest, que

Ytyrt uytruytruyt uiytityuituyi tityityityi t tirtyiteititeyuietuyiet teitueyyyyyyi storeriscid fv storeriscid storeriscid storeriscid storeriscid storeriscid

faccust ibusdan delicipsam doluptatur? Quia eat volles alibus ea alis eum sinusam volorest, que

Table Header	Franklin Gothic	Medium Cond	12 PT
Table Body	Franklin Gothic Book	Regular	10 PT

Ucil inum exerfer rovita ipid et offic tem issus pliquae sincia nobis et que vel inimpor atureicae repelignam, qui ratate vendam quia simus pores nis eumque velent esenita derspereius quibus, sa nullaut que escite necus amenduntio et ducil ex explant que quos et, exerchit, iunto experspe peraturibus, quid est, veriorpore exeriam, sequia sapis volorehent, tem adis ante omnis ea consequ idendam endeliscium dus, sus, il in nimagnis ipiendiostia cum expliquam assitat dem atus ut elit eum nusdand ipicabo. Fic tem vel ium aut fugia que preiur aliquas ent, qui guatusam endis moluptisquis mo esciendant porrum fugit dolor aut guae. Itatinulla susantin esti cum in con eos magnis et exere aut volori comnisc itendeles volupta dolut eseguiae nos non et, quis voluptate pore volorrumquam harumqui dis rectatur?

Fugitiur? Quis reped ulparum nulluptati utam harit modite nis de praeror moluptiation nat mossiti nobitin ullabor eribusam accatem. Ment, qui vellam, sectorehende vel inctetur? Qui site seque non coneturiatem enisiti alia sequam, sim nosandu ciendit quo omniet, odi doloresequi blaccae volorem quibustem sam, omnis volorior alis perspictatur re magnima quis apitate mi, sin nossi rectio vereptam, everenis ullorro quia consecus, aliatii storeriscid erspid que volo mos et as ne pa si idendigendus asincto odi volorepratem asperci raectus ea earibea aut laut

For each map (including local and regional maps), the following guidelines will be adhered to for content and style including all of the required elements outlined below. Additional elements might be necessary depending on the purpose of the map (discussed below). The TMP study area map will follow the guidelines for style shown in the sample map.

### Figure AA-1: Sample Impact Area Map

## Layout Features

- Project Title
- Scale bars
- North arrow
- Legend along bottom

### **Required Map Elements**

- Water features
- Jurisdictional boundaries
- State (where applicable)
- County
- Municipal
- Major roads
- Interstate
- Toll
- U.S.
- State
- County roads, if impacted
- Passenger rail lines and stations
  - NJ Transit
  - PATH
  - Light Rail / PATCO
  - MTA
- Major airports
- Ports

### **Additional Map Elements if Applicable:**

- Freight rail lines applicable where freight movement along rail is relevant, including movements from ports
- Local roads applicable for smaller study areas where additional detail might be desirable



## Transportation Management Plan Guidelines

# **Appendix B**

Figure BB-1: Traffic Engineering Organizational Chart



11/16/2017

# Appendix C

This appendix provides a full list of potential strategies adapted from Section 4 (Work Zone Impact Management Strategies) of the FHWA TMP Template, found at:

http://www.ops.fhwa.dot.gov/wz/resources/final rule/tmp examples/sample tmps/sec c.htm#4.

## **Temporary Traffic Control**

- 1. Construction phasing/staging
- 2. Full roadway closures
- 3. Lane shifts or closures
- 4. One-lane, two-way controlled operation
- 5. Two-way, one-lane traffic/reversible lanes
- 6. Ramp closures/relocation
- 7. Freeway-to-freeway interchange closures
- 8. Night work
- 9. Weekend work
- 10. Work hour restrictions for peak travel
- 11. Pedestrian/bicycle access improvements
- 12. Business access improvements
- 13. Off-site detours/use of alternate routes
- 14. Temporary signs
- 15. Arrow boards
- 16. Channelizing devices
- 17. Temporary pavement markings
- 18. Flaggers and uniformed traffic control officers
- 19. Temporary traffic signals
- 20. Lighting devices
- 21. Other area projects
- 22. Utilities
- 23. Right-of-Way
- 24. Other transportation infrastructure
- 25. Design-Build
- 26. A+B Bidding
- 27. Incentive/Disincentive clauses
- 28. Lane rental
- 29. Performance specifications
- 30. Prefabricated/precast elements
- 31. Rapid cure materials

**Transportation Operations** 

- 1. Transit service improvements 2. Transit incentives 3. Shuttle services 4. Parking supply management 5. Variable work hours 6. Telecommuting 7. Ridesharing/carpooling incentives 8. Park-and-Ride promotion 9. Signal timing/coordination improvements 10. Temporary traffic signals 11. Street/intersection improvements 12. Bus turnouts 13. Turn restrictions 14. Parking restrictions 15. Truck/heavy vehicle restrictions 16. Reversible lanes 17. Dynamic lane closure system 18. Ramp closures 19. Railroad crossing controls 20. Coordination with adjacent construction site(s) 21. Late lane merge 22. PCMS with speed display 23. Travel time estimation system 24. Advanced speed information system 25. Advanced congestion warning system 26. Conflict warning system (i.e., construction vehicles entering roadway) 27. Travel time monitor system 28. Freeway queue monitor system 29. CCTV monitoring 30. Real-time detour 31. Speed limit reduction/variable speed limits 32. Temporary traffic signals 33. Temporary traffic barrier 34. Movable traffic barrier systems 35. Crash cushions 36. Temporary rumble strips 37. Intrusion alarms 38. Warning lights 39. Automated flagger assistance devices (AFADs) 40. Project task force/committee 41. Construction safety supervisors/inspectors 42. Road safety audits 43. TMP monitor/inspection team
  - 44. ITS for traffic monitoring/management

45. TMC

- 46. Surveillance (i.e., CCTV)
- 47. Helicopter for aerial surveillance
- 48. Traffic Screens
- 49. Call boxes
- 50. Mile-post markers
- 51. Tow/freeway service patrol
- 52. Total station units
- 53. Photogrammetry
- 54. Media coordination
- 55. Local detour routes
- 56. Contract support for Incident Management
- 57. Incident/Emergency management coordination
- 58. Incident/Emergency response plan
- 59. Dedicated (paid) police enforcement
- 60. Cooperative police enforcement
- 61. Automated enforcement
- 62. Increased penalties for work zone violations
- 63. Emergency pull-offs

### Public Information and Outreach Public Awareness Strategies

- 1. Branding
- 2. Press kits
- 3. Brochures and mailers
- 4. Press releases/media alerts
- 5. Mass media (earned and/or paid)
- 6. Paid advertisements
- 7. Project Information Center
- 8. Telephone hotline
- 9. Planned lane closure website
- 10. Project website
- 11. Public meetings/hearings, workshops
- 12. Community task forces
- 13. Coordination with media/schools/business/emergency services
- 14. Work zone education and safety campaigns
- 15. Work zone safety highway signs
- 16. Rideshare promotions
- 17. Visual information

### **Motorist Information Strategies**

- 18. Radio traffic news
- 19. Changeable message signs
- 20. Temporary motorist information signs
- 21. Dynamic speed message sign

- 22. Highway Advisory Radio (HAR)
- 23. Extinguishable Signs
- 24. Highway information network (web-based)
- 25. Traveler information systems (wireless, handheld)
- 26. Transportation Management Center (TMC)
- 27. Live traffic camera(s) on a website
- 28. Project information hotline
- 29. Email alerts